

ACTIVITY: Crane - Truck Mounted - Hiab		SWMS No.:		
SAFE WORK METHOD STATEMENT (SWMS) -	Part 1			
Company Name: Switchboard Tranz	Address: PO Box 6043, Upper Mt G	avatt, Qld 4122		ABN: 18 066 447
Company Contact: Jason Flynn	Position: Director			Phone No.: 0411 61 51 00
Project Details				
Project:				
Job Address:				
Job Description:			_	Insert Photo
Relevant workers must be consulted in the development, app	proval and communication of this SWMS:		SWMS Approved	by Employer/PCBU/Director/Owner.
Name: (Include names of workers Signature:	Job Title:	Date:	Print Name	
who were consulted in relation to the				
development of this SWMS)			Signature:	
			Date:	
Name of Principal Contractor:	Principal Contractor Compar	<mark>y Name:</mark>		
Date SWMS provided to Principal Contractor:	Principal Contractor Signatur	Principal Contractor Signature:		
Name of person responsible for ensuring compliance with S	SWMS: Signature:			Date:

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
			© SafetyCulture All Rights Reserved		



SWMS Scop	00						Hig	gh Ris	sk Construction Wo	ork	
hazardous man be developed fo There are seve should be cons	overs the general u nual tasks, traffic mar or these tasks, and for and types of Vehicle- idered when choosin e cranes or common AS 1319-1994 Safe	nagement or rig or any risks not of -Mounted Truck ng the type of o brand names (s	ging and dogging in covered in this SWM Loader Cranes and rane for the job. Th such as Hiab or Palfi Ensure all PPE meet	sufficient det IS. d each has s ne cranes are inger). Personal l ts relevant Au	tail. Dedicate pecific safet also knowr Protective Istralian Stat	ed SWMS sho y devices, wi by other name Equipme adards. Inspe	hich mes nt (PPE)	ork": Movin Work corric Is can blace P	ng Plant carried out adjacent to a lor rried out on or near ener	ollowing "High Risk Cor a road, railway or shipping gised electrical installatior t http://www.saiglobal.com	lane, traffic
	Foot Protection	Hearing Protection	High Visibility	Head Protection		Eye tection	Hand Protecti		Sun Protection	Rings, watches, jewellery that may	
				EY					Broad brimmed hat, UV rated clothing, SPF 30+ sunscreen, tinted safety glasses with adequate UV protection)	become entangled in machines must not be worn. Long and loose hair must be tied back.	
Diesel is class Compensation Australian Code classified as Ha	Goods / Hazardo ssified as a hazard Council (ASCC) an e for the Transport of armful. Read the Sa recommendations ar	dous chemical nd is not classi f Dangerous Go fety Data Shee	according to the fied as a Dangero ods by Road or Rail ts (SDS) for all fue l	us Good acc I (ADG Code)	cording to . Diesel is	due to incor Diesel is to environment	ironmenta rect dispo xic to aqu Noise p	al risks sal of, uatic or collutio	or from run-off of hazar rganisms, may cause le	o waterways and water c dous chemicals during sp ong-term adverse effects is conducted in close pro ctions in urban areas.	ills or clean up. in the aquatic
Hazards - Wi	hat can cause harm	n? Risks -	What can happen	?	Control I	leasures t	o Reduc	ce Ris	k		
 Structural fa component, hydraulic ra 			- C a - If a	onsult with th ssociated with represented ny consultation	e person y n the task by an elec on	you are cted He	alth and Safety Represe	or on the potential hazards Intative (HSR), they must l	be included in		



 Contact or collision with other plant and structures Electricity Noise Hazardous Manual Tasks Hazardous Chemical – single exposure (Diesel, lubricants) Static electricity. 	 Hearing Loss Muscular stress/ Musculoskeletal Disorder Explosion causing injury or death Single exposure to hazardous chemical causing illness or death. 	Liaise with Principal Contractor to establish that the following on-site systems and procedures are in place: Health and Safety rules Induction for all workers – site specific Supervisory arrangements Communication Injury reporting Hazard reporting Personal Protective Equipment Exclusion Zones Risk Assessments SWMS and JSA's.
		 Assess the exposure of workers to noise, including the frequency of exposure to noise levels that exceed the legislated Exposure Standard while operating the truck mounted loader crane and determine required controls such as Audiometric Testing and PPE. Refer to Noise Control SWMS for detailed information regarding the prevention of hearing loss and legislative requirements. Audiometric Testing. If Audiometric testing is required it must: Be provided within three months of the worker commencing work Be started before people are exposed to hazardous noise (such as new workers or those changing jobs) Provide a baseline as a reference for future audiometric test results Have follow-up tests carried out at least every two years. Be carried out with consultation with your workers and their health and safety representatives Be carried out by competent persons in accordance with the procedures in the relevant Australian Standard Workers should be given the results of audiometric testing accompanied by a written explanation of the meaning and implications.
		 National Certification may be required (including slinging and lifting of loads) for operation. Nationally Accredited Certification is required to operate the following types of Vehicle-Mounted Truck Loader Cranes: Any crane above 10 metre tonnes * Non-slewing mobile crane above 3 tonnes Slewing mobile cranes (up to 20 tonnes), (up to 60 tonnes) (up to 100 tonnes) (open/over 100 tonnes). * To calculate Metres Tonnes – Load x radius = Lift performance rating (in metre tonnes).

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
			© SafetyCulture All Rights Reserved		



All operators to be trained, licensed and competent to safely operate the truck mounted loader crane,
Training should include:
- Site specific induction (include location of amenities, first aid facilities, emergency plans and
evacuation points, incident reporting, communication, contact persons etc)
- Health and Safety Rules for site
 Supervisory arrangements
 PPE requirements for site
 Types of hazards at site
 Site plans – showing no go zones for pedestrians
- Traffic Management plans
 Relevant SWMS and JSA's
 Site security requirements
- Read and understand the manufacturers manual/safety precautions for the truck mounted loader
crane.
Operator must be FULLY conversant with:
 The manufacturer's recommendation and rating charts for the crane
 The safety devices present on the crane.
 The PCBU and the Principal Contractor will be required to determine, establish, control and monitor the following: Scope of work Appropriate Crane for the work to be carried out Ground conditions and supporting structures are adequate to support the weight of the crane and loads while conducting the planned lifts Crane operators hold the relevant licence and is competent to operate the crane or cranes Weather conditions, e.g. the likelihood of high winds or thunderstorms Best location for the crane to carry out the planned lifts, e.g. where are buildings, other structures and plant at the workplace, aeroplane flight paths Adequate room for the crane, equipment, people and other mobile plant and vehicles to enter and exit the workplace safely Liaison with electricity supply authorities about control measures for working near overhead electric lines Enough trained, licensed and competent people supporting safe crane operations.
Ensure work undertaken at construction sites complies with the requirements of the site (including induction cards, Safe Work Method Statements etc).

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
			© SafetyCulture All Rights Reserved		



		Detailed Risk commenceme	Assessment and SWMS to be developed, with consultation with relevant vent of the job.	vorkers, before
		RB: 4A	Person responsible to implement control measures: Jason Flynn Site Safety Officer: Principal Contractor:	RA: 2M
Job Step: Preparation	1			
 Hazards include: Moving / falling objects Structural failure - A crane component, including the boom, jib, hydraulic rams or wire rope could suffer structural failure without warning Crane - Overturning Contact or collision with other plant and structures Electricity Noise Hazardous Manual Tasks Hazardous Chemical – single exposure (Diesel, lubricants) Static electricity. 	 Risks include: Struck or crushed by moving / falling objects causing death or serious injury Contact or collision with other plant and structures causing death or serious injury Electric shock/ electrocution Hearing Loss Muscular stress/ Musculoskeletal Disorder Explosion causing injury or death Single exposure to hazardous chemical causing illness or death. 	covered: - Exc and - Dec con - Use - All I Inspection o - Ang - Gro - Loa - Suf - Suf - Pla - Suf - Pla - Ade - Ens - Suf - Ens - Suf - Ens - Suf - Ens - E	Inside the provided and the provided and pro	es as per site plan) work zone and badways flow as required ures and plant at or recent rain,

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
© SafetyCulture All Rights Reserved					



	- Can - Is no - If reo	not see the path of travel of the load or the crane ot in a position to make an accurate judgement of distance quired for operating in near proximity to exclusion zones of power lines.	orkers crane
	operator 1. "Tiger Tai the proxin 2. Power cal If working with The exclusion specified on th	s, labourers etc.) the following must be considered: Is" can be installed prior to commencement (Note: Tiger tails ONLY give a visu hity of power lines.) ples can be redirected or power isolated for the duration of the work. hin the exclusion zone of live power lines an Authorised Person is required as a zones and approach distances to overhead electricity lines at the locations a be site plan are to be clearly identifiable and enforced by a dedicated controller.	al warning of Spotter. nd distances
	the area and b on a Risk Asso must be sough Lane closures traffic authority	being injured by the crane or falling objects. The size of the exclusion zone should essment. Where the exclusion zone is a public footpath or roadway to be closed at from the relevant authority. People should be safely directed to an alternative and other operations requiring barricades and signs to be erected should meet γ , local government authorities and relevant building or local laws. Refer to relev ecific details on safe work near overhead power lines.	d be based approval ootpath. ocal road
	RB: 4A	Person responsible to implement control measures: Jason Flynn Site Safety Officer: Principal Contractor:	RA: 2M
ion			
 Risks include: Struck or crushed by moving / falling objects causing death or serious injury Contact or collision with other plant and structures causing death or serious injury 	continuing isol Hearing prote - It is - It is - It s c	ation of the power supply is obtained. ection, ensure: worn by all persons throughout the period of exposure to noise suitable for the type of working environment and the work tasks comfortable and correctly fitting for the worker	
	 Struck or crushed by moving / falling objects causing death or serious injury Contact or collision with other plant and structures causing death or 	 Can Is no. If rec Overhead Poo operator "Tiger Tai the proxim Power cal If working with The exclusion specified on the area and bo on a Risk Assemust be sough Lane closures traffic authority Practice for sp RB: 4A RB: 4A Bo not work in continuing isol Hearing proteins of the series and structures causing death or serious injury Contact or collision with other plant and structures causing death or on structures causing death or on structures causing death or on the structures causing death or the structures causing death or the structures causing death or the structures causend the structures causend the structures cause the structure	RB: 4A Site Safety Officer: Principal Contractor: Principal Contractor: ion Do not work in No Go Zones of electrical power lines unless de-energised/isolated and evidence continuing isolation of the power supply is obtained. Risks include: Do not work in No Go Zones of electrical power lines unless de-energised/isolated and evidence continuing isolation of the power supply is obtained. - Struck or crushed by moving / falling objects causing death or serious injury Do not work in No Go Zones of electrical power lines unless de-energised/isolated and evidence continuing isolation of the power supply is obtained. - Contact or collision with other plant and structures causing death or - It is worn by all persons throughout the period of exposure to noise - It is suitable for the type of working environment and the work tasks - It is comfortable and correctly fitting for the worker

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
		(© SafetyCulture All Rights Reserved		



 Crane - Overturning Contact or collision with other plant and structures Electricity Hazardous Manual Tasks Hazardous Chemical – single exposure (Diesel, lubricants) Static electricity. 	 Electric shock/ electrocution Muscular stress/ Musculoskeletal Disorder Explosion causing injury or death Single exposure to hazardous chemical causing illness or death. 	Ensure work area is barricaded from other mobile plant. If required (such as roadside work) adequate traffic management is provided. Where work is undertaken in close proximity to power lines: - Trained spotters - Movement limiters installed. Ensure work area is clear of obstructions. Pre-operation check to be carried out by the Licenced Crane Operator. Visually check for: - Evidence of structural weaknesses such as paint separation and/or weld stress - Boom and jib for straightness and any evidence of physical damage, such as cracking, bending, or any other deformation of the welds - All guards are in place - Wire rope for damage including sheaves, drums rigging, hardware, and attachments - Hooks for deformity or cracks. If found they must be removed from service - Oil and hydraulic leaks - Tyre damage and inflation - Clean windows, lights and rear view mirror - Loose objects inside of cabin - Rubbish and dirt in the engine compartment, radiator and the cabin daily - Log book entries. Always inspect boom hoist lockout and other operator aids, such as anti-two-block devices (ATB) and load moment indicators (LMI), for proper operation and calibration. Axle Lockouts – Where fitted: - Should be regularly checked to ensure that they are functioning correctly. Inspect before use. Ensure: - Equipment, including labelled controls and safety devices, are present and working - Complete log books - Slings, chains, lifting equipment in acceptable condition, rated for the loads to be lifted and compatible. Ensure: - Operator on opposite side to where the load is being lifted/lowered - Clear view of load at all times - Load cannot become entangled/snagged - Truck tray is clear of loose materials (such as lashings, dunnage and packing material) and
		 Truck tray is clear or loose materials (such as lasnings, dunnage and packing material) and suitable access is provided. Outriggers/Stabilisers: Ensure outriggers/stabilisers are used as per the manufacturers recommendations.

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:	
© SafetyCulture All Rights Reserved						



		Outriggers/stabilisers MUST be lowered and on firm footing.		
		NOTE: Whee	Is should not be lifted off the ground as they supply the main stability.	
		- Truck	ng brake is applied. wheels are chocked if the ground slopes slightly uate tyre pressure. Person responsible to implement control measures: Jason Flynn Site Safety Officer: Principal Contractor:	RA: 3H
Job Step: Lifting Gear Checks				
 Hazards include: Moving / falling objects Structural failure - A crane component, including the boom, jib, hydraulic rams or wire rope could suffer structural failure without warning Crane - Overturning Contact or collision with other plant and structures Hazardous Manual Tasks. 	 Risks include: Struck or crushed by moving / falling objects causing death or serious injury Contact or collision with other plant and structures causing death or serious injury Muscular stress. 	suitable to kee - It is ta - Tags (WLL) - Lifting - Shacl - Lifting - Lifting - Sling i All damaged I Documented Flat synthetic - No k - Prot	agged to identify the date of the lifting gear's last inspection list all relevant information (e.g. for a chain sling includes grade of chain, rated ca), manufacturer, chain size and any relevant Australian Standard marking) I hooks are provided with operable safety latches where appropriate kles used as terminal fittings are prevented from unscrewing I eyes and inserts are compatible I slings are not damaged, e.g. excessive wear, damaged strands, cracks, deform e corrosion is appropriate for load being lifted, including adequate capacity and protection from si ifting gear is to be removed from service and tagged. Lockout-Tagout (LOTO). maintenance records for the lifting gear should be available at the workplace.	apacity nation or harp edges.

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
		(© SafetyCulture All Rights Reserved		



		 wear or other damage. Wire rope slings: Check the twists or lay of the sling. If ten randomly distributed wires in one lay are broken, or five wires in one strand of a rope lay are damaged, the sling must not be used Check end fittings and other components for any damage that could make the sling unsafe. Chains/hooks: Links are free from bends and or twists No gouges, chips and cuts in links Check for wear at bearing surfaces on links. Tag lines are: At least 16 mm diameter & non conductive Maintained in clean and dry condition. Spreader beams (Strut for spreading double leg slings). Check: Safe working load (SWL) and tare weight which should be clearly stenciled on the beam For visible damage. 			
		RB: 4A	Site Safety Officer: Principal Contractor:	RA: 3H	
Job Step: Crane Setup	Dista in shada	One was stability	4		
 Hazards include: Moving / falling objects Structural failure - A crane component, including the boom, jib, hydraulic rams or wire rope could suffer structural failure without warning Crane - Overturning Contact or collision with other plant and structures Electricity Hazardous Manual Tasks. 	 Risks include: Struck or crushed by moving / falling objects causing death or serious injury Contact or collision with other plant and structures causing death or serious injury Electric shock/ electrocution Muscular stress/ Musculoskeletal Disorder. 	- Cra mov - Gro - Mea - Slop - Win crar - Mar the Ensure: - Cra	ty: intain stability is one of the key factors associated with serious crane incidents. Come operation that may result in an overturning movement greater than the stabilis wement of the crane bund conditions ans of supporting the outrigger pads or the crane tyres pe of the ground—both side slope and slope in direction of crane travel and conditions—this will vary depending on the size and shape of the suspended loon ne boom more in which loads are lifted or moved, e.g. when mobilising a load a sudden stop load to swing, destabilising the crane.	ing bad and	

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
			© SafetyCulture All Rights Reserved		



		 Each load is assessed in consultation with associated personnel for the need for a tag hand line. If required, where control of the load is critical, a suitable tag line should be attached. Outriggers must be: Extended, lowered and locked in position BEFORE the boom is erected as per manufacturer's instructions Fully extended. (Note: If the outriggers are not capable of being fully extended the safe operating radius is reduced. The radius should be recorded.) Loads must be checked for: Weight Stability – example – when lifting steel, bricks etc. Other hazards such as hazardous chemicals. 			
		RB: 4A	Person responsible to implement control measures: Jason Flynn Site Safety Officer: Principal Contractor:	RA: 3H	
Job Step: Conduct Trial Lift					
 Hazards include: Moving / falling objects Structural failure - A crane component, including the boom, jib, hydraulic rams or wire rope could suffer structural failure without warning Crane - Overturning Contact or collision with other plant and structures Electricity Noise Hazardous Manual Tasks. 	 Risks include: Struck or crushed by moving / falling objects causing death or serious injury Contact or collision with other plant and structures causing death or serious injury Electric shock/ electrocution Hearing Loss Muscular stress/ Musculoskeletal Disorder. 	Mounting and - Fac - Maii - Use - Nev - Nev - Nev - Dor - Dor - Dor whe - Sea Ensure:	er conditions – do not work in extreme weather. Dismounting from the Mobile Crane cabin: e the cabin ntain a three-point contact with the steps and with handholds the handrails and steps provided er mount a moving crane er dismount a moving crane er jump off the crane not use the steering wheel as a hand hold not carry tools or supplies when you try to mount / dismount not use any controls as handholds when you enter the operator compartmer en you exit the operator compartment t belts must be worn. v freely suspended loads are to be lifted	t or	
			mple - Never attempt to remove a tree that has been partly dug out.		

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
		(© SafetyCulture All Rights Reserved		



		 Check: With load lifted slightly off the lifting plane (ground, truck tray, roof etc.) Boom is correctly positioned to ensure load to be lifted is plumbed under the hook. This will ensure that the load does not swing when lifted. Load is correctly slung All crane equipment is functioning properly. Hydraulic or pneumatic systems (where relevant) are at the required operating pressure. Where load-measuring devices are fitted, the estimated weight is verified and load/radius calculations are revised as required. Note: A trial lift is important particularly for near capacity loads or loads of unusual weight distribution or shape. If the trial lift reveals an unacceptable operational situation, lower the load and take corrective action. 		
		RB: 4A	Person responsible to implement control measures: Jason Flynn Site Safety Officer: Principal Contractor:	RA: 3H
 Job Step: Operation of Crane Hazards include: Moving / falling objects Structural failure - A crane component, including the boom, jib, hydraulic rams or wire rope could suffer structural failure without warning Crane - Overturning Contact or collision with other plant and structures Electricity Noise Hazardous Manual Tasks. 	 Risks include: Struck or crushed by moving / falling objects causing death or serious injury Contact or collision with other plant and structures causing death or serious injury Electric shock/ electrocution Hearing Loss Muscular stress/ Musculoskeletal Disorder. 	- Avo - Avo - Avo - Use - Use - Reg Operation as p Loads must no Suspended loo Keep clear of - Patt - Area - Patt	anual Handling: id long periods of repetitive movements id awkward and sustained positions id prolonged sitting mechanical lifting aids when possible two or more people for lifting & moving heavy / awkward equipment ular breaks. ber manufacturer's recommendations and task specific safe work method state ever exceed the rated capacity of the crane and equipment. ads must never be left unattended. the danger zones during operation: n of the load a beneath the suspended loads of crane components veen the vehicle and load.	ment.

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:	
© SafetyCulture All Rights Reserved						
			, .			



WARNING: Stability can be affected during the load movement. Monitor throughout operation. Load must be safe / secured before shifting. Check weather conditions – do not work in extreme weather.
If adverse weather conditions develop during work, such as high winds, heavy rain, and/or extreme temperatures, it may be necessary to close down the lifting operation then immediately cease work.
Operator must remain alert to other plant and equipment movements on the site.
Where possible, avoid working or travelling on sloping or uneven ground. Travel on a slope should be up or down the slope, not across the slope. If working or travelling on a slope is unavoidable, use the crane within the manufacturer's specified capacity for operating on the relevant degree of slope.
 Travelling on site. Where Required: Route must be planned and checked to ensure that the crane traverses only firm and level surfaces. Where slopes are unavoidable, an authorised person must be consulted to ensure the feasibility of operation and the necessary hazard control measures are in place. Road travel. The crane manufacturer's instructions should be followed when preparing a mobile crane for road travel. Precautions for road travel include: Check tyre pressures meet the manufacturer's instructions for road travel Secure the outriggers—both hydraulic and manual—with a locking device specified by the crane manufacturer Stow outriggers in a travelling position to ensure that there is no lateral movement Store loose components in appropriate storage areas Disengage all drives to hydraulic pumps, booms and outriggers All controls in the off position Restrain the boom according to the crane manufacturer's instructions to ensure there is no
unintended movement of the boom. Hazard control measures include:
- Minimum speed
 Gentle accreditation and braking (to minimise load swing).
 Carrying the load near to the ground surface Use of tagline ropes
- Always avoid rapid slewing
 Safe work procedure in place for lifting loads such as:
Material boxes
 Formwork frames Cement tilt up panels
 Joists or bearers
o Timber





Job Step: Re-fuelling Hazards include: - Explosion - Fire - Hazardous Chemical – single exposure (Diesel, lubricants) - Static electricity.	Risks include: - Burns caused by fire - Electric Shock - Explosion causing injury or death - Single exposure to hazardous chemical causing illness or death.	Follow Manufa Additional PI boots, and ap Note:	Jason Flynn Site Safety Officer: Principal Contractor: rent (issue date within 5 years) Safety Data Sheets (SDS) for all acturers Manual for more details for re-fuelling. PE if any risk of splashing - Chemical splash goggles, chemical re ron. id breathing vapours or contact with fuel	·
		A crane shoul - All I - The - All p - The On completion - Folo - Ret - Insp	not be suspended over, or travel over, a person d not be left unattended by the Crane Operator unless: bads are removed from the hook or lifting device hook has been secured or raised to a position where is clear of oth bowered motions have been disabled keys removed or the starting device locked out. on: If the crane into correct transport position ract the stabilisers and stow correctly and locked in position beet all equipment for damage and follow tag out procedures if requi lect plant for signs of malfunction (such as hydraulic leaks) and report Person responsible to implement control measures:	red
		the load unde Loads are to b	 Pipes Plasterboard sheeting Hazardous Materials. stop the load swinging when lifting the load. The Mobile Crane operative control when lowering loads or when the load is suspended. be hoisted and lowered into position using all relevant crane movem te Australian Standards. 	·

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
		(© SafetyCulture All Rights Reserved		



		 Re-fuelling: Shut off engine Allow to cool before re-fuelling if possible Remove cap slowly Use a fuel hose, pouring spout or funnel Fill tank and wipe away excess Ensure there is no over spill Ensure cap has been secured and any vapour residue has been wiped away Check for leaks. Note: Do not eat, drink or smoke after handling fuel until hands are carefully washed. Shower and wash 		and wash
		-	fter work. Wash clothes in separate wash from other clothes.	
			sources include pilot lights, stoves, heaters, cigarettes, matches/lighters, grindin lighting, light switches, radio transmitters, mobile phones, battery powered forklift	
			Person responsible to implement control measures:	
			Jason Flynn	
		RB: 3H	Site Safety Officer:	RA: 2M
			Principal Contractor:	
Job Step: Maintenance				
Hazards include:	Risks include:	Perform sche	duled maintenance as specified by the manufacturer and relevant Australian Sta	ndard.
- Moving / falling objects	- Struck or crushed by moving /		When conducting maintenance of crane arm ensure support pins are in place and	d working, to
- Structural failure - A crane	falling objects causing death or		ental hydraulic pressure release and collapse of equipment.	n la sialativa
component, including the boom, jib, hydraulic rams or wire rope could	serious injury Contact or collision with other plant 		vicing; maintenance and suitably licenced, qualified & competent persons, as pe and manufacturer's recommendations, perform repairs.	riegislative
suffer structural failure without	and structures causing death or		d testing Mobile Cranes must include the:	
warning	serious injury		or inspection required for registrable Mobile Cranes	
- Crane - Overturning	- Electric shock/ electrocution		ular weekly and monthly inspection and testing required for all plant	
- Contact or collision with other plant	- Muscular stress/ Musculoskeletal	- Insp	pection and testing for plant item re-registration.	
and structures	Disorder.		d testing should include:	
- Electricity			ual inspections	
 Hazardous Manual Tasks. 			nmissioning inspection and tests	
		- Roi	itine inspections and maintenance	

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
			© SafetyCulture All Rights Reserved		



	Week All rep Maint shoul		s contactors ecords
	shoul	should include a statement from the appropriate competent person confirming the item of plant has been inspected and is safe to operate.	
		wte: Inspection intervals recommended in manufacturer's publications frequently represent minervals for average operating conditions and should be used as a guide to actual operating conditions Person responsible to implement control measures:	
	RB:	B:4A Site Safety Officer:	RA:3H
Emergency Procedures / Emerg		Principal Contractor:	
Emergency Procedures / Emerg	ency Response		

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
© SafetyCulture All Rights Reserved					



Emergency Response: Call 000 immediately if a person is entrapped, has been crushed or has been hit by Mobile Crane or its load.	Develop site-specific rescue procedures/SWMS
Do not attempt to rescue a person who is trapped or has been crushed by a load or Mobile Crane unless Emergency Services personnel have provided direction and it is safe to do so.	Ensure all workers on-site are trained and familiar with emergency and evacuation procedures.
Procedure must be in place which covers electrocution / electric shock and/or contact with overhead electrical wires or associated structures.	Person/s responsible to implement and follow emergency procedures and control measures:
Develop and implement an emergency response plan for the site. Include:	
- Assembly points	Jason Flynn
- Communication	
- Consultation methods	Site Safety Officer:
 Responsible persons 	
 Emergency contacts - names and phone numbers 	Principal Contractor:
 First aid equipment 	
 Fire Extinguishers – accessible & serviced. 	

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
© SafetyCulture All Rights Reserved					



Review

To ensure controls are implemented and monitored effectively:

- Toolbox /pre-work meetings will be undertaken
- Relevant persons will be consulted on hazards and contents of SWMS, work
 plans and other applicable information
- Control measures will be monitored throughout works:
 - Spot checks
 - Consultation
 - Scheduled audits
- Corrective actions will be recorded and rectified in a timely manner SWMS will be reviewed and updated accordingly (in consultation with relevant persons)

Ensure all controls are reviewed as per the following:

- If controls fail to reduce risk adequately
- When changes to the workplace or work activity occur that create new / different risks where controls may no longer be effective
- New hazards identified
- After an incident involving work activities relevant to this SWMS
- During consultation with relevant persons indicate review is needed
- A Health and Safety Representative (HSR) requests a review in line with the requirements of the legislation.

Person/s responsible to implement and follow monitoring and review procedures and control measures:

Jason Flynn

Site Safety Officer:

Principal Contractor:

SAFE WORK METHOD STATEMENT - Part 2

Formal Training, Licences required for workers undertaking this task:	Duties of workers undertaking this task:	Details of Supervisory Arrangements for workers undertaking this task:
 Licence to Perform High Risk Work (operating certain plant, equipment) – n/a TAFE or other recognised training organization: Major Training Certificate Construction Induction Card (or equivalent) - yes Competent in operation of make/model of plant - yes Emergency procedures – emergency response - yes PPE - yes Traffic Management Plans – n/a 	(Name): Operator (Name: Clean-up crew (Name): Supervisor	 Suitably qualified supervisors for job Direct on-site supervision Remote site - communication systems/ schedule Audits Spot Checks, etc. Reporting systems

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
© SafetyCulture All Rights Reserved					



Details of: regulatory permits/licenses Engineering Details/Certificates/WorkCover Approvals:	Relevant Legislation, Codes of Practice: Note: Retain only the legislation references applicable	e to your state of operation for this SWMS.
 Local council permits - n/a Building Approvals – n/a EPA approvals/permits - n/a Certain plant to be registered with State Authority – n/a PPE comply with relevant Australian Standards Plant/Tools/Equipment: (List plant and equipment to be used on the job.) Vehicle Mounted Truck Loader Crane Make / Model: PK14002 Palfinger Crane Make / Model: 2008 ProRanger 10 Hino 	 Commonwealth, NSW, QLD, ACT Work Health and Safety Act 2011 Work Health and Safety Regulations 2011 Northern Territory Work Health and Safety (National Uniform Legis Act 2011 Work Health and Safety (National Uniform Legis Regulations SA, Tasmania Work Health and Safety Act 2012 Work Health and Safety Act 2012 Work Health and Safety Regulations 2012 Codes of Practice: Safe Work Australia (2011): Construction Work First Aid in the Workplace Managing the Risk of Falls at Workplaces Managing Noise and Preventing Hearing Loss in Workplace How to Manage Work Health and Safety Risks Hazardous Manual Tasks Managing the Work Environment and Facilities WHS Consultation, Cooperation & Coordination 	 Western Australia Occupational Safety & Health Act 1984 Occupational Safety & Health Regulations 1996 Codes of Practice: Australian Standards: As 2550.3:2011 Cranes, hoists and Winches – Safe Use – General requirements AS 2550.3: 2011 Cranes, hoists and Winches – Bridge, gantry, portal (including container cranes), jib and monorail cranes AS 2550.2:2002 Cranes, hoists and winches - Safe use Part 5: Mobile Cranes AS/NZS 1418.5: 2002 Cranes, hoists and winches – Mobile cranes AS/NZS 1418.5: 2005 Occupational noise management AS/NZS 4501:2008 (set) Occupational Protective Clothing AS/NZS 3775.2:2004 Chain slings – Grade T – Care and use. (plus amendment 1 – 2006)
Reference Documents	·	
Safe Work Australia (2011): <i>Guidance on the Classificat</i> Safe Work Australia (2011): Code of Practice: <i>Managin</i> Safe Work Australia (2011): Code of Practice: <i>Managin</i> Safe Work Australia (2011): Code of Practice: <i>Hazardo</i>	g Noise and preventing hearing loss at work	DRAFT - Safe Work Australia (2013): Code of Practice: Cranes Work Health & Safety Queensland: Technical Guidance Note: Safe Operation of Cranes WorkCover NSW: Guide: Cranes, Hoists and Winches Cargotec, Inc. (1993): Operator's Manual: Hiab 710

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
		(© SafetyCulture All Rights Reserved		



SAFE WORK METHOD STATEMENT - Part 3

This SWMS has been developed in consultation and cooperation with *employee/workers* and relevant *Employer/Persons Conducting Business or Undertaking (PCBU)*. I have read the above SWMS and I understand its contents. I confirm that I have the skills and training, including relevant certification to conduct the task as described. I agree to comply with safety requirements within this SWMS including risk control measures, safe work instructions and Personal Protective Equipment described.



DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:
© SafetyCulture All Rights Reserved					



RISK ASSESSMENT MATRIX

HB 436:2004 Risk Management Guidelines Tables 6.3 – 6.8 reproduced with permission from SAI Global under licence 1210-c062. Standards may be purchased at http://www.saiglobal.com References: Safe Work Australia (2011) - Code of Practice: How to Manage Work Health and Safety Risks, AS/NZS 31000 -2009 Risk Management Principles and Guidelines.

Step 1: Determine Likelihood What is the possibility that the effect will occur?				
	Criteria	Description		
Almost certain	Expected in most circumstances.	Effect is a common result.		
Likely	Will probably occur in most circumstances.	Effect is known to have occurred at this site or it has happened.		
Possible	Might occur at some time.	Effect could occur at the site or I've heard of it happening.		
Unlikely	Could occur at some time.	Effect is not likely to occur at the site or I have not heard of it happening.		
Rare	May occur only in exceptional circumstances.	Effect is practically impossible.		

Step 2: Determine Consequence What will be the expected effect?						
Level of Effect:	Example of each level:					
Insignificant/Acceptable	No effect – or so minor that effect is acceptable.					
Minor	First Aid treatment only; no lost time injury.					
Moderate	Medical treatment; serious injuries, temporary partial disability; lost time injury < 7 days.					
Major	Hospital admittance; extensive injuries; lost time injury > 7 days; Permanent Total Disability injury; death.					
Catastrophic	Multiple Permanent Total Disability injuries; multiple deaths.					

Step 3 Determine the risk score						Stan / Pagard rick soore on workshoet (Nate Dick soores have no absolute value and should			
Consequence						Step 4 Record risk score on worksheet (Note – Risk scores have no absolute value and should only be used for comparison and to engender discussion.)			
Likelihood	Insignificant	Minor	Moderate	Major	Catastrophic				
Almost certain	3 High	3 High	4 Acute	4 Acute	4 Acute	Score	Action		
Likely	2 Moderate	3 High	3 High	4 Acute	4 Acute	4 A: Acute	DO NOT PROCCED. Requires immediate attention. Introduce further high level controls to lower the risk level. Re-assess before proceeding.		
Possible	1 Low	2 Moderate	3 High	4 Acute	4 Acute	3 H: High	Review before commencing work . Introduce new controls and/or maintain high level controls to lower the risk level. Monitor frequently to ensure control measures are working.		
Unlikely	1 Low	1 Low	2 Moderate	3 High	4 Acute	2 M: Moderate	Maintain control measures. Proceed with work. Monitor and review regularly, and if any equipment/people/materials/work processes or procedures change.		
Rare	1 Low	1 Low	2 Moderate	3 High	3 High	1 L: Low	Record and monitor . Proceed with work. Review regularly, and if any equipment/people/materials/work processes or procedures change.		

DOCUMENT NO: 10133	VERSION NO: 2	ACTIVITY: Crane – Truck Mounted - Hiab	AUTHORISED BY:	REVIEW NO:	DATE:				
© SafetyCulture All Rights Reserved									